



■粉河高区配水池

R3	<ul style="list-style-type: none"> 粉河高区配水池更新1期工事 46,178,000円 擁壁工(重力式・嵩上)89m・ブロック積工27m(造成面積388㎡) DIPGX φ 250 40.5m(配水管)・φ 200 36.9m(送水管)
R4	<ul style="list-style-type: none"> 粉河高区配水池更新2期工事 126,819,000円 ステンレス全溶接型パネル配水池 1池 500㎡(13,000×8,000×5,500H) DIPGX φ 250 28m(配水管)・φ 200 31m(送水管)
R5	<ul style="list-style-type: none"> 粉河高区配水池更新3期工事 30,000,000円(予算) 電気計装設備(水位計・流量計等)